

RFP 29-22

ADDENDUM 02

Macomb County Administration Building Repairs

Q 1. I have a question regarding the electrical portion of the project scope, specifically the fire alarms. What fire alarm system is required and who monitors the alarms?

Alarm company- Cintas Fire Protection

Keynotes 4 & 10 shown next to double doors being replaced.

4. Temporarily disconnect and remove Fire Alarm pull stations to facilitate new door. Protect wiring and save device for reinstallation. See new work.

10. Reinstall existing fire alarm pull station on mullion. Extend conduit and wiring as required. Provide all testing and commissioning of existing fire alarm system for services rendered.

Keynote 13 shown next to new revolving door (or double door for alternative)

13. Mount new fire alarm pull station on mullion at 48" AFF and connect to existing building fire alarm system. Route wiring in mullion to floor level below or above ceiling as deemed by site conditions. Remove and reinstall existing lay-in ceiling tiles as required for new conduit installation. Provide fire stop for all penetrations thru fire rated walls and floors.