

September 18, 2023

ADDENDUM NO. ONE to the plans and specifications for the WARREN CONSOLIDATED SCHOOLS, DEMOLITION OF VARIOUS STRUCTURES, Warren, MI, Architect's Project No. 231986 dated August 25, 2023

The above plans and specifications are modified, supplemented, or augmented as follows, and this ADDENDUM NO. ONE, is hereby made a part of the contract documents.

**PRE-BID SIGN IN SHEET**

**ITEM NO. 1** Attached, please find the Pre-Bid Sign in Sheet

**RESPONSES TO PRE-BID RFI'S**

**ITEM NO. RFI #1:** Please confirm if a planner is already involved from DTE/Consumers:

Answer: The Owner has contracted the various utility companies regarding shut-off.

**ITEM NO. RFI #2:** Who is responsible for gas line disconnect and cap?

Answer: Contractor to be responsible for this scope per keynotes on drawings.

**ITEM NO. RFI #3:** Who is responsible for all electrical disconnects from buildings and back to transformer or main feed?

Answer: Contractor to be responsible for this scope per keynotes on drawings.

**ITEM NO. RFI #4:** Please confirm testing is by the Owner, i.e., compaction and concrete.

Answer: The Owner is procuring a Testing Company. The Contractor shall arrange the schedule for testing with the Owners Testing Company.

**ITEM NO. RFI #5:** Please provide dimensions for concrete replacement.

Answer: New replacement sidewalk and curb and gutter shall be installed across removed driveway openings, driveway approach to be backfilled, re-graded and restored as lawn - typical at all locations.

Concrete sidewalk replacement:  
Convent = 360 sq. ft.  
House = 375 sq. ft.

L.F. Curb replacement:  
Convent = 40'  
House = 100'

Attachments – Pre-Bid Sign in Sheet

**END OF ADDENDUM NO. 01**

Cc: Nick Pitrone, Warren Consolidated Schools  
Ron Zuhorski, Plante Moran Cresa